

MYSORE DIVISION.

Dated 30th July 1910.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 31st August 1910, for constructing a combined building for Local Fund Dispensary and Wards with out-houses at Nanjangud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore, between the hours of 12 noon and 4 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a combined building for Local Fund Dispensary and In-patient Wards with out-houses at Nanjangud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	Per	Dispensary and Wards	Kitchen	Dead-house
		Quantity	Quantity	Quantity
1. Earthwork (excavation and filling basement) ...	C. yd. ...	126	8	17
2. Concrete work to foundation ...	C. ft. ...	1,182	...	...
3. Burnt stone in chunam (foundation and basement) ...	Do ...	3,078	290	537
4. Brick in chunam (superstructure) ...	Do ...	5,595	298	309
5. Armoured concrete work ...	Do ...	257	...	...
6. Teakwood moulds for preparing armoured concrete, etc. ...	Lump sum	...	...	...
7. Iron work for chowkats, etc., to be locally made ...	l/o	...	...	...
8. Burnt stone slabs ...	S. ft. ...	999	31	88
9. Reinforced concrete work with portland cement for roofing ...	C. ft. ...	689	...	...
10. Iron work including freight and fitting charges ...	Cwt. ...	19'34	4'21	7'6
11. Threading and finishing tie rods of main roof complete ...	Lump sum	...	...	...
12. Finishing tie rods, etc., with bolts and nuts complete of curved roof and angle iron ...	Each ...	88	...	...
13. Finishing the inside projections of doors and windows with portland cement wash up to 6 feet high ...	Lump sum	...	...	...
14. Chunam plastering ...	Square ...	86'51	5'74	5'61
15. Filling in the angles in rooms ...	Lump sum	...	...	...
16. Flooring with Cuddapah slabs on 3" concrete bed and cement pointing ...	Sqr. ...	15'22	...	1'50
17. Raising masonry wall over concrete, slab, complete ...	Lump sum	...	...	...
18. Teakwood panelled doors ...	S. ft. ...	226	18	...
19. Do windows panelled shutters outside and glazed shutters inside with iron bars complete ...	l Do ...	184	...	...
20. Do ventilators with glazed shutters ...	Do ...	62	...	...
21. Whitewashing two coats ...	Sqr. ...	49'83	2'54	5'61
22. Color-washing do ...	Do ...	86'68	2'76	...
23. Ornamental iron finials ...	Each ...	12	...	...
24. Painting to iron work ...	Lump sum	...	...	...
25. Chocolate painting ...	Sqr. ...	9'43	1'45	1'02
26. Inscription ...	Lump sum	...	...	...
27. Roofing with 1st class Mangalore tiles, excluding reapers ...	Sqr. ...	...	2'06	3'57
28. Ridge tiles set in mortar ...	R. ft. ...	...	15	17
29. Ventilating tiles ...	Each ...	...	4	2
30. Flooring with concrete with smooth plastering ...	C. ft. ...	...	35	...
31. Burnt stone slabs table sloping towards centre, nicely dressed and polished for dissecting bodies ...	Do ...	...	...	10
32. Teakwood battened doors ...	S. ft. ...	...	...	18
33. Do windows battened with iron bars, glazed shutters inside, etc., complete ...	Do ...	...	...	9
34. Do large window frames fitted with gauge wire netting ...	Do ...	...	...	24
35. Do windows, ordinary, with battened shutters ...	Do ...	...	4	...
36. Poling rafter ridges, drilling holes, bolts and nuts ...	Each ...	...	1	...
37. Holding down bolts 18" long and $\frac{1}{2}$ " diameter with anchor plates ...	Do ...	...	4	4
38. Folding angle iron reapers, drilling holes, revet and revetting complete ...	Do ...	...	48	88
39. Honeycomb work ...	Sqr. ...	...	...	2'51
40. Couping rafters at ridge ...	Lump sum	...	...	...
41. Threading tie rods complete ...	Do ...	...	...	...
42. Wrought iron pipe for connecting the table ...	R. ft. ...	...	...	12
43. Levelling ground ...	Lump sum	...	...	...
44. Constructing compound wall of the type approved by the Chief Engineer ...	Do ...	...	...	...
45. Latrine ...	Do ...	...	...	...
46. Rain-water pipes ...	Do ...	...	...	...
47. Excavating well ...	Do ...	...	...	...
48. Constructing cisterns in Examination and Compounding Room ...	Do ...	...	...	...
49. Constructing chimney in kitchen ...	Do ...	...	...	...

R. V. SUNDARAM IYER, Executive Engineer.